

MUNICIPAL CORPORATION OF BHILAI

N.I.T.

वार्ड 44 श्रद्धा मान्देशवरी स्कूल से गौरा गौरी चौक तक सीमेंटीकरण कार्य।

(As Per PWD Road SOR 15.06.2026)

S.N.	Itme Code	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	3.2	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all leads & lifts as per relevant clauses of section 300.						
			1	50.00	3.00	0.30	45.00	Cum
2	6.3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)						
		P.C.C. M-10	1	100.00	3.00	0.10	30.00	Cum
3	6.4	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base as per approved mix design and finising to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum						
			1	622.00	3.00	0.10	186.60	Cum
4	1.1	Transportation of metal i/c loading & unloading						
		For a lead upto 1 Km.					33.75	Cum

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai

