

OFFICE OF THE MUNICIPAL CORPORATION BHILAI
NIT

वार्ड 14 सड़क 28 के पास नाला में पुलिया निर्माण कार्य।

CG PWD BUILDING SOR 10.06.2026

S NO	Item	Qty	Unit
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.in all types of soil		
		31.500	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.		
		2.520	Cum
3	Providing and laying nominal mix cement concrete with crushed stone aggregate using concrete mixer in foundation, plinth and at ground level excluding cost of form work.		
	1:3:6 (1 cement : 3 coarse sand : 6 graded stone aggregate 40mm nominal size).		
		3.360	Cum
4	Providing and laying nominal mix reinforced cement concrete with crushed ston aggregate using concrete mixer in all works upto plinth level excluding cost of form work.		
	1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).		
		44.268	Cum
5	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:		
		4426.800	KG
6	Foundations, footings, base of columns and plinth beam in any shape and size.		
		14.000	Sqm
7	Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)		
		49.400	Sqm

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai