


MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :- वार्ड क्र. 61 (पूर्व) सेक्टर 8 मिलाई पूर्व खनित बोर में जी.आई. पाइप द्वारा लाइन का विस्तारीकरण कार्य।

As Per PWD Building/ELEC SOR 10.6.2026			
S.N	PARTICULARS	QTY	UNIT
1	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete:		
	15 mm dia. nominal bore	720	M
	20 mm dia. nominal bore	80	M
	25 mm dia. nominal bore	1050	M
	32 mm dia. nominal bore	60	M
	40 mm dia. nominal bore	60	M
2	Supplying and laying following sizes one number FRLS PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1). 2 x 6 sq. mm	250	m


सहायक अभियन्ता
नगर पालिक निगम, भिलाई


उप अभियन्ता
नगर पालिक निगम, भिलाई