MUNICIPAL CORPORATION BHILAI

NIT

1

1.13

कार्य का नाम :–वार्ड क्रमांक 33 संतोषी पारा केम्प 02 भिलाई यादव मोहल्ला विवेकानंद नगर केम्प 02 भिलाई में भवन का संधारण कार्य।

Based on PWD/SOR 10.06.26 (Building Works) Electrification Work 10.6.2026

Item No.	Particulars of item	Qty.	Unit
1	2	7	9
1	Demolishing cement concrete including disposal of material within 50 metre lead.1:3:6 or richer mix	4.55	m^3
2	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :	9.00	Sqm
3	Providing and applying on exterior surface with ECONOMY Exterior Emulsion paint of required shades to give protective and water proof finish minimum three coats applied @ 1.43 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian Ace , Dulux Promise Exterior , Berger Wall Masta , Nerolac Suraksha Plus , Nippon Shogun Opus, One Style Power Bright) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work (With 2 Year Warranty)	9.00	Sqm
4	Providing and applying for renewing on exterior surface with PREMIUM Exterior emulsion paint of required shade to give protective and water proof finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian Apex , Dulux Weather Shield Prima E900, Berger Weathercoat Antidust , Nerolac Everlas Excel , Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.Two coats applied @ 0.75lit / 10Sqm up to final finish	140.00	Sqm
5	Providing and applying for renewing Acrylic washable Distemper or lite economy Plastic emulsion paint having VOC content less than 50gms/ lit as per relevant I.S. Code 428:2000 (product such as Tractor Uno, Dulux acrylic distemper, Berger Bison, Opus Style/ lite economy emulsion product such as Asian Tactor Spark , Dulux Pomise sheen, Neroloc Litil Master, Berger Bison Lite, Nippon Superio.) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.Two coats up to final finish applied @ 0.750Kg/ 10Sqm	111.00	Sqm
6	Providing and applying 2mm thick white cement based polymeric Exterior grade Putty with minimum 3 coats applied @ 5.4 kg/ 10Sqm as per relevant IS code 17545:2021 (Product such as Birla wall care, Asian trucare, JK wall putty, Berger Bison wall putty) to make the surface smooth and even with all tools tackles and labour etc. complete for the work.	9.00	Sqm

Scanned with CamScanner

Item No.	Particulars of item	Qty.	Unit
1	2	7	9
7	Providing and fixing steel door/ window with M.S. sheet 1mm thick, frameof angle iron, diagonal braces of angle/ flat iron of suitable size, 3.00mm M.S. gusset plates at junctions and corners, all necessary fittingscomplete including applying a priming coat of red oxide zinc chromateprimer.	50.00	Kg
8	Providing and applying Glossy finish Enamel paint mimimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian Apcolite Premium Enamel , Dulux Promise Premium Enamel , Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.	18.48	Sqm
9	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth levelexcluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.10	Cum
10	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415	8.00	Kg
11	Providing and fixing M.S. grill of approved pattern made of M.S. flats orsquare or round bars welded to steel frame of windows etc. including applying a priming coat welded to frame with all necessary fitting complete including applying a priming of red oxide zinc chromateprimer.	30.00	Kg
12	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.50 mm thick	91.00	Sqm
13	Providing and laying glazed viitrfied floor (GVT/PGVT) with digital print of random design with water absorption less than 0.05% and conforming to IS:15622-2017 of 1st quality of approved make in all colours, shades and size mentioned below (+/- 10mm), laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse sand) including grouting the joints with white cement and matching pigments etc complete.	80.64	Sqm

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई

Scanned with CamScanner