MUNICIPAL CORPORATION, BHILAI
NIT

(5)

कार्य का नाम :– वार्ड 52 सेक्टर 04 भिलाई सड़क नं0 4 में पेयजल हेतु पाईप लाईन विस्तारीकरण कार्य।

0.65

As per P.W.D. Building S.O.R. W.E.F. 10.06.2026

S.No.	Details of Item	UOM	Quantity
1	Demolishing cement concrete including disposal of material within 50 metre lead.1:3:6 or richer mix	Cu	9.00
2	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soils.	Cu	12.00
3	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	Cu	6.00
4	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	Cu	6.00
5	Providing and laying in trenches G.I. pipes medium class complete with G.I. fittings including excavation of trenches, refilling the same and testing of joints complete: (Page- 177, Item-19.9.2)		
a	15mm dia. nominal bore	M	38.00
b	20mm dia. nominal bore	M	40.00
C	25mm dia. nominal bore	M	228.00
6	Providing and fixing brass/gun metal gate valve with C.I. wheel of approved quality (screwed end):25 mm nominal	Nos	5.00
7	Providing and fixing G.I. Union in G.I. pipe (New work) including cutting and threading the pipe and making long screws etc. complete: 25 mm nominal	Nos	5.00
8	Providing and fixing G.I. Union in existing G.I. pipe line, cutting and threading the pipe and making long screws including excavation, refilling the earth or cutting of wall and making good the same complete wherever required : 25 mm nominal	Nos	5.00

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाइ

Scanned with CamScanner