(6)

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

1.69

कार्य का नामः– वार्ड क्रमांक 52 सेक्टर 03 भिलाई सड़क नं. 10 में ब्लॉक 16 व 5 के मध्य सी.सी. रोड निर्माण कार्य।

	PWD Road SOR 15.06.2026		
A	CC ROAD		
S.No.	ITEM	Qty.	UNIT
1	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base a per approved mix design and finising to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum	41.99	Cum

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाइ

Scanned with CamScanner