(8)

कार्य का नामः— वार्ड क्र. 55 सेक्टर 02 भिलाई सड़क नं. 01 और 02 में नाली पुलिया का निर्माण कार्य।

1.69

	PWD BUILDING SOR 10.06.2026		
S.No.	ITEM	Qty.	UNIT
1	4).Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 500D&415	85.2	KG
2	4).Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawingsincluding cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 550D	1275.1	KG
3	6).Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depthconsolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	6.14	CUM
4	7).Carriage by mechanical transport upto 5 km lead:	26.1136	CUM
5	5).Providing and fixing form work including centring, shuttering, strutting,staging, propping bracing etc. complete and including its removal at alllevels, for:Foundations, footings, bases of columns plinth beam, curtain wall in anyshape and size and all type of wall below plinth level.	123.21	SQM
6	1).Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.1.1.1 In all types of soils.	38.57	CUM
7	1).Providing and fixing form work including centring, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for:Suspended floors, roofs, access platform, balconies (plain surfaces) and shelves (cast in situ)	2.1	SQM
8	2).Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.372	CUM
9	3).Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.585	CUM
10	3).Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mmnominal size).	13.1	CUM
11	Extra for precast PCC/ RCC work of any mix including form work, hoisting and fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishing with cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand) but excluding reinforcement.	5.93	CUM

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई

Scanned with CamScanner