MUNICIPAL CORPORATION BHILAI (C.G.)

1.19 (9)

NIT

कार्य का नामः– वार्ड क्र. 55 सेक्टर 02 सड़क नं. 09 और 14 के समीप सार्वजनिक नाली निर्माण कार्य।

	PWD BUILDING SOR 10.06.2026		
S.No.	ITEM	Qty.	UNIT
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.1.1.1 In all types of soils.	39.2	CUM
2	Providing and laying nominal mix plain cement concrete with crushedstone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	4.48	CUM
3	Providing and laying nominal mix reinforced cement concrete with crushedstone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mmnominal size).	12.9	CUM
4	Extra for precast PCC/ RCC work of any mix including form work, hoistingand fixing in Cement Mortar. 1:2 (1 Cement : 2 coarse sand) and finishingwith cement plaster in Cement Mortar 1:3 (1 Cement : 3 coarse sand)but excluding reinforcement.	6.72	CUM
5	Providing and placing in position reinforcement for R.C.C. work includingstraightening, cutting, bending, binding etc. complete as per drawingsincluding cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 550D	1332.8	KG
6	Providing and fixing form work including centring, shuttering, strutting,staging, propping bracing etc. complete and including its removal at alllevels, for:Foundations, footings, bases of columns plinth beam, curtain wall in anyshape and size and all type of wall below plinth level.	134.4	SQM
7	Filling from available excavated stuff (Excluding rock) in trenches, plinth,sides of foundation etc. in layers not exceeding 20cm in depthconsolidating each deposited layer by ramming and watering with a leadupto 50 M. and lift upto 1.5 M.	6.72	CUM
8	Carriage by mechanical transport upto 5 km lead:	24.36	CUM

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाइ

Scanned with CamScanner