MUNICIPAL CORPORATION OF BHILAI

NIT

(12)

कार्य का नाम :– वार्ड क्रमांक 56 (पश्चिम) सेक्टर–02 सड़क नं. 15 बी में रोड किनारे पाथवे में पेवर ब्लॉक लगाने का कार्य।

284

As Per PWD Building SOR 10.06.26

S.N.	PARTICULERS OF ITEMS	Quantity	UOM
1	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soil	68.70	Cum
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	22.90	Cum
3	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	34.35	Cum
4	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks	229.00	Sqm
5	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	9.32	Cum
6	Carriage by mechanical transport upto 5 km lead:Earth	35.72	Cum

कार्यपालन अभियंता	सहायक अभियन्ता	उप अभियन्ता
नगर पालिक निगम, भिलाई	नगर पालिक निगम, भिलाई	नगर पालिक निगम, भिलाइ

Scanned with CamScanner