NAGAR PALIK NIGAM BHILAI

NIT

वार्ड क्रं. 22 नकटा तालाब से अकक्षरधाम मंदिर तक सीसी रोड निर्माण कार्य।

(As per P.W.D ROAD S.O.R. W.E.F. 15.06.2026)

S.N.	PARTICULAR	Q	U
	C.C. ROAD		
1	Excavation in Soil (by Mechanical Means.) Excavation for roadway in soil using mechanical means including loading in tipper for carrying of cut earth to embankment site and unloading with all lifts and lead upto 1000 meters as per relevantclauses of section 300.		
		92.75	**cum**
2	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads P.C.C. M-10		
		92.75	**cum**
3	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base a per approved mix design and finising to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum		
		139.13	**cum**
4	Transportation of metal i/c loading & unloading		
	For a lead upto 1 Km.	**64.93**	**cum**

ASSTT.ENGINEER
Nagar Palik Nigam, Bhilai

SUB ENGINEER
Nagar Palik Nigam, Bhilai