MUNICIPAL CORPORATION OF BHILAI

N.I.T.

वार्ड क्र. 42 गौतम नगर तेलगू मोहल्ला के विभिन्न गलियों में सीसी रोड निर्माण कार्य।

(As Per PWD Road SOR 15.06.2026)

S.N.	Itme Code	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	6.3	Providing and laying cement concrete for plain concrete/ reinforced concrete i/c form work, shuttering complete in as per drawings and specifications.(For Village roads)						
	(i)	P.C.C. M-10						
			1	48.00	3.00	0.10	14.40	
						G.Total	**14.40**	**Cum**
2	6.4	Providing and laying Un-reinforced Cement Concrete without Dowel bars including formwork and expansion, contraction & longitudinal joints as per design and as per IRC-62, over a prepared base a per approved mix design and finising to lines and grade as per Drawing for Pavement thickness less than 200mm in Low Volume Roads. With Cement concrete grade M-30 and minimum cement content @ 375 kg/cum						
			1	340.00	3.50	0.15	178.50	
						G.Total	**178.50**	**Cum**

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai

Scanned with OKEN Scanner