MUNICIPAL CORPORATION OF BHILAI

N.I.T.

वार्ड 48 खुर्सीपार में बीएसपी पानी टंकी के पीछे केनाल रोड स्थित गार्डन का जीर्णोद्धार कार्य।

(As Per PWD BUILDING SOR 10.06.2026)

S.N.	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	Repairs to plaster in patches of area 2.5 sq. metres and under including cutting the patch in proper shape, raking out joints and preparing and plastering the surface of the walls with cement mortar 1:4 (1 cement : 4 fine sand) complete including disposal of rubbish to the dumping ground within 50metres lead :						
	Thickness upto 15mm					200.00	
					G. Total	200.00	sqm
2	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).						
						50.00	
					Total	50.00	cum
28	Providing & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq.cm Pigment Coloured (rubber mould) precast interlock concrete blocks						
		2	50.00	3.00		300.00	
					G.Total	300.00	sqm
36	Providing and applying on exterior surface with PREMIUM Exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coats applied @ 1.40 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian Apex , Dulux Weather Shield Prima E900 , Berger Weathercoat Antidust , Nerolac Everlas Excel , Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and articleand cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work.(With 3Year Warranty.)						
						300.00	
					G.Total	300.00	sqm
49	Supplying and stacking of good earth at site including royalty, loading, unloading and carriage upto 5 km (earth measured in stacks will be reduced by 20% for payment).						
		1	80.00	15.00	0.50	600.00	
					G.Total	600.00	cum
51	Supplying and stacking at site well decayed cow dung manure from approved source, including loading, unloading and carriage upto 5 km (manure measured in stacks will be reduced by 8% for payment).						
						200.00	
					G.Total	200.00	cum
	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.						
	In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.					500.00	
					G.Total	500.00	KG
	Providing and applying satin/ matt finish Enamel paint mimimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.						
						50.00	
					G.Total	50.00	Sqm
52	Providing and planting following herbs in garden including preparation of soil, base plantation, providing and spreading different fertilizers, soil and sand						
a	Hedges like Alife, Dorenta, Tikoma etc					100.00	
					G.Total	100.00	each

Scanned with OKEN Scanner

b	Furn like Arica, China etc (3 year old)					115.00	
					G.Total	115.00	each
c	Carpet grass (well developed)						
						1200.00	
					G.Total	1200.00	sqm

Executive Engineer
Municiapal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai

Scanned with OKEN Scanner