(1)

MUNICIPAL CORPORATION BHILAI

NIT

कार्य का नाम :–कार्य का नामः– जोन कमांक 03 अंतर्गत वार्ड कमांक 32 बैकुंठधाम तालाब में छठ घाट का रंग रोगण का संधारण कार्य। 3.37

Based on PWD/SOR 10-06-2026 (Building works)

Item No.	Particulars of item	Qty.	Unit
1	2	3	4
1	Providing and applying renewing exterior floor surface with PREMIUM HEAVY DUTY ACRYLIC exterior emulsion paint of required shade of one coats applied @ 0.75 lit / 10Sqm up to final finish as per relevant I.S.Code 15489:2013 (Product such as Asian Apex Floor Guard , Dulux Floorplus , Berger Weathercoat Floor Protector , Indigo platium Series) with all tools tackles and labour etc.complete for work.	4480.00	Sqm
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	90.00	Cum

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई

Scanned with CamScanner