MUNICIPAL CORPORATION OF BHILAI

NIT

कार्य का नाम :—वार्ड क 67 पश्चिम, सेक्टर 07 में सड़क एवेन्यू–ए के पास स्थित उद्यान का संधारण कार्य करने बाबत्।

(As Per PWD Building SOR 10.6.2026 & Electric SOR 10.06.2026)

S.NO	PARTICULAR	QTY	UNIT
1	Providing and fixing M.S. grill of approved pattern made of M.S. flats or square or round bars welded to steel frame of windows etc. including applying a priming coat of red oxide zinc chromate primer	150.00	kg
2	12mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	15.00	sqm
3	15mm thick cement plaster of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	15.00	sqm
4	Supplying and stacking sludge at site including royalty, loading, Unloading and carriage upto 5 km (sludge measured in stacks Will be reduced by 8% for a ment	168.00	sqm
5	Providing and applying on exterior surface with ECONOMY Exterior Emulsion paint of required shades to give protective and water proof finish minimum three coats applied @ 1.43 lit / 10Sqm up to final finish as per relevant I.S Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian Ace , Dulux Promise Exterior , Berger Wall Masta , Nerolac Suraksha Plus , Nippon Shogun Opus, One Style Power Bright) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work (With 2 Year Warranty)	100.00	sqm
6	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	1.20	Cum
7	Brick work with modular fly-ash lime bricks (FaLG Bricks) confirming to IS:12894-2002 of class designation 4.0 in foundation and plinth in. Cement Mortar 1:6 (1 Cement : 6 Coarse Sand)	1.00	Cum
8	Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.In all types of soils	21.84	Cum
9	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.12	Cum
0	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.(Note :Excess/ less cement used as per design mix is payable/recoverable separately) 1:1½ 3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size) 1:11/2 3 (1cement :11/2 coarse sand :3 graded stone aggregate 20 mm nominal size).	3.10	Cum
11	Carriage by mechanical transport upto 5 km lead: 1.26.1 Earth	16.8	Cum
12	Prov.ding and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc complete	36	Cum
13	Prov.ding & laying 60mm thick precast interlocking concrete blocks of approved size (approx 305 sqcm) and shape/ pattern, over 40 mm thick average complete coarse sand bed with joints of 3mm thick filled by fine sand including leveling with surface vibrator, temping and sweeping etc. complete of minimum compressive strength of 250 kg/sq cmPigment Coloured (rubber mould) precast interlock concrete blocks	80	Sqm
14	Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio ≥ 120 lumens /watt 180 watt	4	Each
15	Supplying of following 230/250 volts LED street light 90 watt	6	Each
16	Supplying and laying following sizes one number FRLS PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).2 x 6 sq. mm	100	Mtr.

17	Supplying and laying following sizes one number FRLS PVC insulated/ XLPE, PVC sheathed, unarmoured, aluminium conductor power cable of 1.1 KV grade on surface/ existing cable tray with 1 mm thick GI saddle as per specification, IS 1554 (1988, Part 1) / IS 7098 (1988, Part 1) 4 x 10 sq. mm	90	Mtr.
18	Providing and fixing in position chain linked steel wire fabric made of 4mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete Aperture 50x50mm	75.00	Mtr.

कार्यालय नगर पालिक निगम, भिलाई

क्रं./उद्यान विभाग/न.नि./2026 1065 भिलाई दिनांक – 06/11/26

आयुक्त नगर पालिक निगम भिलाई की ओर से एकीकृत पंजीयन प्रणाली अंतर्गत सक्षम श्रेणी में पंजीकृत ठेकेदारों से निम्नलिखित कार्य हेतु दिनांक 26/11/2026 को सायं 5.30 बजे तक मुहरबंद निविदा आमंत्रित की जाती है। प्राप्त निविदा दिनांक 27/11/2026 को प्रातः 11.00 बजे खोली जावेगी।

नोट :– निविदादाता लिफाफा में पत्र व्यवहार का पूर्ण पता अनिवार्य रूप से अंकित करें।

क्र.	कार्य का नाम	निविदा लागत	धरोहर राशि	निविदा प्रपत्र का मुल्य	समयावधि	निविदा फार्म
1	वार्ड क्रं. 67 पश्चिम, सेक्टर 07 में सड़क एवेन्यू–ए के पास स्थित उद्यान का संधारण कार्य करने बाबत्।	2.78	4000.00	750	60 दिन	फार्म ए

कार्यपालन अभियंता
नगर पालिक निगम
भिलाई