

(2)

MUNICIPAL CORPORATION BHILAI (C.G.)

NIT

2.95

कार्य का नाम:- वार्ड क्रमांक 35 भैरव बस्ती लोहार गली, अन्ना गली में नाली संधारण कार्य।

PWD BUILDING SOR 2026

A	nali nirman		
S.No.	ITEM	Qty.	UNIT
1	1).Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.1.1.1 In all types of soils.	86.45	CUM
2	2).Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	13.3	CUM
3	3).Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded	30.8	CUM
5	4).Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawingsincluding cost of binding wire in foundation and plinth all	2156	KG
6	5).Providing and fixing form work including centring, shuttering, strutting,staging, propping bracing etc. complete and including its removal at alllevels, for:Foundations, footings, bases of columns plinth beam, curtain wall in anyshape and size and all type of wall below plinth level.	252	SQM
7	6).Filling from available excavated stuff (Excluding rock) in trenches, plinth,sides of foundation etc. in layers not exceeding 20cm in depthconsolidating each deposited layer by ramming and watering with a lead	12.60	CUM
8	7).Carriage by mechanical transport upto 5 km lead:	66.465	CUM

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई