

(4)

**MUNICIPAL CORPORATION BHILAI (C.G.)
NIT**

**कार्य का नाम:- जोन क्रमांक 36 बनारसी चाय के पास सर्विस रोड के किनारे नाली
निर्माण एवं संधारण कार्य।**

1-18

PWD BUILDING SOR 10.06.2026,

S.No.	ITEM	Qty.	UNIT
1	1).Excavation for all types and sizes of foundations, trenches and drains or for any other purpose including disposal of excavated stuff upto 1.5 m lift and lead upto 50m (at least 5m away from the excavated area), including dressing and leveling of pits.1.1.1 In all types of soils.	33.75	CUM
2	2).Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	3.00	CUM
3	3).Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mmnominal size).	14.00	CUM
4	4).Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawingsincluding cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 550D	700.00	KG
5	5).Providing and fixing form work including centring, shuttering, strutting,staging, propping bracing etc. complete and including its removal at alllevels, for:Foundations, footings, bases of columns plinth beam, curtain wall in anyshape and size and all type of wall below plinth level.	100.00	SQM
6	6).Filling from available excavated stuff (Excluding rock) in trenches, plinth, sides of foundation etc. in layers not exceeding 20cm in depthconsolidating each deposited layer by ramming and watering with a lead upto 50 M. and lift upto 1.5 M.	5.00	CUM
7	7).Carriage by mechanical transport upto 5 km lead:	25.88	CUM

कार्यपालन अभियंता
नगर पालिक निगम, भिलाई

सहायक अभियंता
नगर पालिक निगम, भिलाई

उप अभियंता
नगर पालिक निगम, भिलाई