

5

MUNICIPAL CORPORATION BHILAI

NIT

0.5/

कार्य का नाम :- जोन क्रमांक 03 क्षेत्रांतर्गत वार्ड क्रमांक 33 हुड़को क्वाटर संतोषी पारा केम्प-02 भिलाई में
अंदेडकर भवन के पीछे कॉपरेटी के पास चबूतरा निर्माण कार्य।

Based on PWD/SOR10.06.2020 2026 (Building Works)

Item No.	Particulars of item	Qty.
1	2	7
1	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	0.63
2	Providing and filling in plinth with sand/ Crusher dust and hard moorum under floor in layers not exceeding 20cm in depth consolidating each deposited layer by ramming and watering, including dressing etc. complete.	0.63
3	Providing and laying nominal mix reinforced cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.60
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending etc. complete as per drawing including cost of binding wire. All complete. Thermo-Mechanically treated bars FE 415	24.00
5	Brick work with modular fly-ash lime bricks (FaLG Bricks) conforming to IS:12894-2002 of class designation 4.0 in foundation and plinth in: Cement Mortar 1:6 (1 cement : 6 coarse sand) SOR Item No 7.5.4	0.30
6	Providing & fixing of form work l/c centering, shuttering, strutting, staging, Proping bracing etc. complete & removal upto 4 m height	24
7	Providing and making 15mm thick cement plaster on the rough side of single or half brick wall of mix: In Cement Mortar 1:6 (1 cement : 6 fine sand)	25.00
8	Providing and applying on exterior surface with PREMIUM Exterior emulsion paint of required shade to give protective and water proof finish minimum 3 coats applied @ 1.40 lit / 10 Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D, C (Glossy /Semi Glossy finish) (Product such as Asian Apex, Dulux Weather Shield Prima E900, Berger Weathercoat Antidust, Nerolac Everlas Excel, Nippon Sumo Etra, Opus True flex) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work. (With 3 Year Warranty.)	25.00
9	Providing and applying satin/ matt finish Enamel paint minimum 2 coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevant I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel, Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc. complete for the work.	20.00
10	Steel work welded in built up sections/ framed work including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works.	69.00
11	15mm thick Marble stone slab flooring over 18mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including grinding rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above) Pink plain marble.	21.25

कार्यपालन अभियन्ता
नगर पालिक निगम, भिलाई

सहायक अभियन्ता
नगर पालिक निगम, भिलाई

उप अभियन्ता
नगर पालिक निगम, भिलाई