

MUNICIPAL CORPORATION OF BHILAI


NIT

कार्य का नाम :-वार्ड कं. 68 सेक्टर 08 के बैडमिंटन कोर्ट सड़क 03,सड़क 12,सड़क 38,सड़क 51-52 के बीच एवं वॉलीबाल कोर्ट सड़क 5 के संधारण कार्य।

(As Per PWD Building SOR 10.6.2026 & Electric SOR 10.06.2026)

S.NO	PARTICULAR	QTY	UNIT
1	Cement concrete flooring with cement concrete 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate 20mm) finished with a floating coat of neat cement.50 mm thick	150	sqm
2	Providing and applying renewing satin/ matt finish Enamel paint one coats in all surface applying @ 0.75 lit/ 10 Sqm up to required finish as per relevent I.S. code 2932: 2013 of (Product such as Asian satin Enamel, Dulux Promise Premium Enamel , Nerolac Synthatic Enamel, Opus Prime enamel) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackle and labour etc.complete for the work.	390.00	sqm
3	Emulsion paint of required shades to give protective and water proof finish minimum three coats applied @ 1.43 lit / 10Sqm up to final finish as per relevant I.S. Code 15489:2013 Type -2 Class D , C (Glossy /Semi Glossy finish) (Product such as Asian ACE Spark , Dulux Pomise exterior smart, Nerolac Littil Master, Berger Bison Lite, Nippon Superio etc) inclusive of providing abro tape on edges and article and cleaning of door, windows, floor and surface as required with all tools tackles and labour etc. complete for the work (With 2 Year Warranty.)	260.00	sqm
4	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending etc. complete as per drawing including cost of binding wire. All complete.Thermo-Mechanically treated bars FE 415	70.00	kg
5	Supplying of following 230/250 volts LED Flood light fitting with all accessories like driver, heat sink made of die cast aluminium with IP 66 protection and 15 KV surge protection on pole bracket, including connection, earthing, Separate housing for driver etc complete as per specification and P.F. should be greater than 0.9. LED chip efficacy ratio > 120 lumens /watt. 120 watt	8	each
6	Supplying and laying following sizes one number FRLS PVC insulated /XLPE, PVC sheathed, steel armoured, aluminium conductor power cable of 1.1 KV grade in existing RCC/ HUME/ STONEWARE/ METAL/ HDPE pipe as per specification, IS: 1554 (1988, Part 1) / IS: 7098 (1988, Part 1).2 x 16 sq. mm	100	m
7	Providing and fixing in position chain linked steel wire fabric made of 4 mm dia G.I. wire of required width in mesh to concrete/ wooden/ angle iron posts including securing and screwing with 2mm dia G.I. wire, G.I. staples, G.I.U-nails or steel pins etc., complete Aperture 50x50mm	30.00	m
8	Structural steel work in single section including cutting, hoisting, fixing in position and applying a priming coat of red oxide zinc chromate primer.	200.00	kg


Asstt. Engineer
Municipal Corporation
Bhilai(C.G.)


Sub Engineer
Municipal Corporation
Bhilai(C.G.)