

NAGAR PALIK NIGAM BHILAI

NIT

मूलभूत सुविध अंतर्गत वार्ड क्र.-27 शारत्री नगर में आर.सी.सी. पुलिया संधारण कार्य।

(As per P.W.D BUILDING S.O.R. W.E.F.10.06.2026)

S.N.	PARTICULAR	Q	U
1	Demolishing brick masonry including arches, stacking of serviceable material disposal of unserviceable material within 50 metres lead. In cement mortar.	0.80	cum
2	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material within 50 metre lead.	0.50	cum
3	Excavation for all types and sizes of foundations, trenches and drains o.....m (at least 5m away from the excavated area), including dressing and leveling of pits. In all types of soil	5.80	cum
4	Providing and laying nominal mix cement concrete with crushed form work. 1:4:8 (1 cement : 4 coarse sand : 8 graded stone aggregate 40mm nominal size).	1.60	cum
5	Providing and laying nominal mix reinforcement cement concrete with crushed stone aggregate using .. reinforcement and form work.1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	4.00	cum
6	Providing and placing in position reinforcement for R.C.C. work including straightening, cutting, bending, binding etc. complete as per drawings including cost of binding wire in foundation and plinth all complete:Thermo-Mechanically treated bars FE 415	360.00	Kg
7	Providing and fixing form work including centering, shuttering, strutting, staging, propping bracing etc. complete and including its removal at all levels, for: Foundations, footings, bases of columns plinth beam, curtain wall in any shape and size and all type of wall below plinth level.	29.55	sqm
8	Providing and laying nominal mix plain cement concrete with crushed stone aggregate using concrete mixer in all works upto plinth level excluding cost of form work. 1:1½:3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20mm nominal size).	0.75	cum
9	Carriage by mechanical transport upto 5 km lead:		
	Earth	4.06	cum

ASSTT.ENGINEER

Nagar Palik Nigam, Bhilai

SUB ENGINEER

Nagar Palik Nigam, Bhilai