

MUNICIPAL CORPORATION OF BHILAI

N.I.T.

45 बालाजी नगर सड़क 53 अधूरा मंच में ग्रेनाइट एवं अक्कुपल्ली सामाज भवन में टाईल्स लगाने एवं संधारण कार्य।

(As Per PWD Building SOR 10.06.2026)

S.N.	Itme Code	PARTICULERS OF ITEMS	No	L	B	H/D	Quantity	UOM
1	12.78	Providing and laying Matt Glazed finish HOMOGENEOUS ACROSS FULL BODY VITRIFIED floor tiles (heavy duty) with water absorption less than 0.05% and conforming to IS: 15622-2017 of 1st quality laid on 20mm thick cement mortar 1:4 (1 cement: 4 coarse Sand) including grouting the joints with white cement and matching pigment etc. complete.						
	12.78.1	Size 600x600mm thickness 9 to 10mm						
			1	13.50	6.00		81.00	
						G. Total	81.00	Sqm
2	12.45	15 mm thick Table rubbed polished Granite stone slab flooring laid over 20mm (Average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with grey cement slurry including rubbing and polishing etc. complete. (Area of slab should be 0.50 sqm and above)						
	12.45.2	Granite stone black						
			1	21.00		1.00	21.00	
						G. Total	21.00	Sqm
3	12.46	15 mm thick Table rubbed polished Granite stone slab in risers and treads of steps skirting dado and pillars laid on 12mm (Average) thick base of cement mortar 1:3 (1 cement : 3 coarse sand) and jointed with risers and treads of steps and width of stone for skirting and dado shall be equal to the height of						
	12.46.2	Granite stone black						
		step	1				6.00	
						G. Total	6.00	Sqm
4	13.4	15mm thick Granite work (machine cut, table rubbed & mirror polished) for wall lining (veneer work) in cement mortar 1:3 (1 cement : 3 coarse sand) including pointing with cement mortar 1:2 (1 white cement: 2 marble dust) mixed with matching pigment. (Area of slab should be over 0.5 sqm).						
	13.4.2	Granite stone black						
			1	4.50	6.00		27.00	
						G. Total	27.00	Sqm
5	9.57	Providing stainless steel railing/ grill made of S.S. flats, hollow S.S. pipe or square/ rectangular sections of approved design fixing in stair case, balcony or other places with metal fasteners and stainless steel bolts etc complete.						
	9.57.2	SS Grade 304						
			1	10.00	1.30	6.50	84.50	
						G. Total	84.50	Kg

Executive Engineer
Municipal Corporation
Bhilai

Assistant Engineer
Municipal Corporation
Bhilai

Sub Engineer
Municipal Corporation
Bhilai

